ELECTRICAL SYSTEMS COMMISSIONING

Aaron Albritton, BCxP



AARON ALBRITTON, BCXP



- US Navy Nuclear Power Program
- Industrial Electrician
- NETA 3 Test Technician
- Mission Critical Commissioning Provider
- Motz Electrical Testing

PRESENTATION OVERVIEW



CX ORGANIZATIONS AND STANDARDS



UNDERSTANDING THE CX PROCESS



MARKET SPECIFIC CX

ORGANIZATIONS AND STANDARDS

ASHRAE

- Focus mostly on HVAC Cx
- Great for the Cx Process
- Certifies Cx Professionals

AABC/ACG

- Focus mostly on HVAC Cx
- Great for the Cx Process
- Certifies Cx Professionals
- NETA/ANSI
 - Focus on Electrical testing and Cx
 - Certifies Test Technicians







NICET





Uptime Institute

• NECA-90

UptimeInstitute

• IEEE



NFPA



AFCOM





A qualitative process to evaluate, verify, and document equipment and systems are planned, designed, installed, tested, operated, and maintained per the owner's project requirements

ASHRAE Cx Standard Phases



Datacenter Phases (Uptime Institute)




Pre-Design / Design

- Stakeholder meetings
- Owner's Project Requirements
- Basis of Design
- Cx Plan

Construction

- Cx Schedule
- Cx Script
- Equipment selection
- Installation QA/QC
- Pre-Functional Inspections and Tests
- NETA ATS
- Energization Plan
- Startup



Post Occupancy

- Delayed and Seasonal Testing
- Respond to warranty calls
- Update OPR
- Final Report

Ongoing Cx and Operations

- Verify operations in accordance with system design and OPR
- Verify ongoing maintenance is performed

Point to Point

- Trip and Transfer logic
- Relay schemes
- Component testing
- Grounding and Bonding
- Inter-substation communication
- Detailed testing plans
- De-energized testing



Commercial/Industrial

MARKET SPECIFIC CX

Infrared

- Switchgear automation/SOO
- EMMS
- Lighting Controls
- Small generator
- Circuit ID/Panel Schedules
- Egress/Life Safety
- Motors/Starters/VFDs



Datacenter

- Switchgear automation/SOO
- Grounding
- UPS/Generator LB
- Power Quality
- Efficiency (PUE/DCIE)
- EMMS
- BCM
- Infrared
- Integrated Systems

